## BANGALORE DIVISION.

*The 20th July* 1896.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, B. C. W. D. Range, Bangalore, up to 31st July 1896, for constructing a pure-water tank on Guttahalli rock, High Ground, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1896.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's office at Bangalore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a pure-water tank on Guttahalli rock" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

| *Items of work.* | *Per.* | *Quantity.* |
|---|---|---|
| Earthwork excavation | C. yd. | 344 |
| Concrete with surki mortar | C. ft. | 9,304 |
| Brick in surki mortar | ,, | 7,366 |
| Plastering with Portland cement | Sqr. | 142·21 |
| Burnt stone slabs 9″ thick with edge dressed | S. ft. | 527 |
| Do 6″ do | ,, | 8,150 |
| Beams (quarried) | R. ft. | 648 |
| Burnt slabs 3″ thick, dressed | S. ft. | 606 |
| Galvanized iron wire netting in teak frames | ,, | 352 |
| Painting with chunam | Sqr. | 76·07 |
| Trap door (4′ × 6′) | No. | 1 |
| Teak shutters with frames for valve house | S. ft. | 60 |
| Iron staircase | No. | 1 |
| *Steps.* | | |
| Excavation, foundation | C. yd. | 2 |
| Stone in clay | C. ft. | 51 |
| Brick in chunam | ,, | 83 |
| Plastering with chunam | Sqr. | 1·66 |
| Slabs for steps (4″ thick dressed) | S. ft. | 39 |
| Clearing site, removing boulders and stepping rock, &c. | Lump sum | |

H. D. RICE, *Sub-Asst. Engr., B. C. W. D. Range.*

## BANGALORE CITY MUNICIPALITY.

*Notices, dated 18th May* 1896.

Parties desirous of undertaking the execution of works, supply of materials, tools, &c., to the City Municipality, are invited to register their names and addresses in the office of the Municipal Commission, fort, where a book is kept for that purpose. Office hours 11 to 5-30 P. M.

---

In view of facilitating delivery of replies to petitions sent to President, City Municipality, petitioners are recommended to apply in person to the Manager, at the office, after the lapse of eight days of presenting such petitions. In cases where replies are not forthcoming, petitioners should bring the same to the notice of the President at once in person. A memo will be posted in the Municipal office building for the information of petitioners, showing dates on which petitions are disposed of.